BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name of Work: **Reserve fund for emergency work in ward no.13** (Desilting & Resetting of Footpath slabs from Dasarahalli main road in ward no.13, Shettyhalli Sub Division.)

Sl. No	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Removing and resetting of Footpath slab. Complete as per specifications.	Sqm	824.58	97.52	Rupees Ninety Seven and Fifty Two Paise Only
2	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed Complete as per specifications.	Cum	978.00	124.02	Rupees One Hundred Twenty Four and Two Paise Only
3	Removing B.S.Slab of drain and stacking etc., Complete as per specifications.	Sqm	558.90	49.18	Rupees Forty Nine and Eighteen Paise Only
4	Refixing Stone slabs of drains and pointing in CM 1:3 etc., Complete as per specifications.	Sqm	558.90	68.74	Rupees Sixty Eight and Seventy Four Paise Only
5	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	Sqm	126.72	1600.00	Rupees One Thousand Six Hundred Only
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 3 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading Complete as per specifications.	Cum	390.00	74.07	Rupees Seventy Four and Seven Paise Only

Note: The said work for sanctioned estimate cost Rs.05.00 Lakhs (Rupees Five Lakhs Only) (Incl.10%+1%KRIDL Charges + 1% Quality control tests Charges) based On "Approved SR Rates"

Signature of the EXECUTIVE ENGINEER-2
KRIDL, BBMP, Bangalore

Executive Engineer,
Dasarahalli Division,